



Case Study: Building Project **Chesterfield Coach Station**

Contract	Chesterfield Coach Station
Client	Chesterfield Borough Council
Engineer	Chesterfield Borough Council
Contract/Value	£500,000
Carried out	October 2004 to April 2005

Description

This high profile scheme to provide a new coach station for Chesterfield was built for Chesterfield Borough Council.

The works involved the construction of a reinforced concrete retaining wall clad with locally sourced masonry, supporting the raft foundation for the main building.

The building superstructure consisting of a timber frame, clad with brickwork and timber panelling was designed incorporating 'green' materials where possible, with natural ventilation using a wind catcher system, sheep's wool insulation and solar panels providing a portion of the building running costs.

Internally finished to a high standard using custom made joinery furniture the project was completed on schedule and within budget.